



824 East Main Street
PO Box 759
Ephrata, PA 17522

Phone: 1-800-352-8196
Fax: 717-733-0959

E-mail: sales@weaverprecast.com
www.weaverprecast.com

Building Better Basements

September 13th, 2006

Volume 1, Issue 1

Introducing Superior Walls by Weaver Precast

Building with Superior Walls Workshop

You're invited to attend Weaver Precast's Superior Walls interactive workshop. This workshop is designed to:

- Introduce you to the Superior Advantage of Superior Walls
- Reduce "surprises" of using a new product before they occur
- Watch how your Superior Walls are built during a Plant Tour
- Q & A session to answer any questions you may have about Superior Walls
- You will receive a \$250 certificate off your first order after attending this workshop

The Workshop is held every 3rd Wednesday of each month from

9 am – 1 pm

*Lunch will be provided / Seating is Limited

To Register go to:

www.weaverprecast.com/workshop.htm and complete the Workshop Form.



In 1985 newly established Weaver Precast was a way for Weaver Masonry to reenter the residential construction market.

Weaver Precast is licensed to manufacture and install the Superior Walls® system in SE Pennsylvania, Delaware, Maryland, & N Virginia and the Epic™ Wall system in Florida.

Superior Walls® foundation system is designed primarily for below grade basement wall applications in new home construction. A revolutionary product, each foundation is custom made to customer specifications. The Epic™ Wall system, in contrast to Su-

perior Walls®, is an above grade application with a class 5 hurricane wind resistance rating, making it an excellent product for the above ground building markets of Florida and the South.

Beginning at 67 basements per year, Weaver Precast has grown to produce and install over 3,700,000 lineal feet of walls in homes throughout the Mid-Atlantic region. In the fall of 2002, Weaver Precast built a new 69,000 sq. ft. expansion of the Ephrata production facilities and a new corporate headquarters which allowed Weaver

to double its capacity and manage the growing business with greater ease and efficiency. In the spring of this year we opened a brand new manufacturing facility in Spartanburg, SC which services South Carolina and Georgia.

For more information on Superior Walls by Weaver Precast visit us at www.weaverprecast.com.



Extreme Makeover: Home Edition

Weaver Precast, Inc. committed to participate in the Extreme Makeover, Home Edition on March 11th. Ken Dewey, owner of Dewey Home contacted Gary Weaver to discuss the project and the family. Located in Northeast Philadelphia, the Py family, William, Carole and their three orphaned grandchildren, would receive a beautiful new home. Their

existing home, plagued by asbestos and lead problems, would be demolished and rebuilt in a remarkable seven days.

In less than two weeks from the initial phone conversation on the 11th, our staff participated in multiple meetings with ABC, the builder and a multitude of other subcontractors that would be par-

ticipating in the project. The project consisted of 271 lineal feet of 4'0" walls.

March 24th was "show time" for Weaver Precast. The Extreme Makeover projects have been labeled by ABC and other builders as the "Superbowl of the Construction Industry."

Continued on next page.

The Future of Foundation Technology Available Today!



Superior Walls by Weaver Precast Inc.

824 East Main Street
PO Box 759
Ephrata, PA 17522

Phone: 1-800-352-8196
Fax: 717-733-0959

E-mail:
sales@weaverprecast.com

Extreme Home Makeover Cont.

Friday the 24th was our "Superbowl." We were scheduled with a five hour time slot to install our wall system beginning at 8pm. Due to unforeseen challenges on the jobsite, we were unable to start our installation until 9pm. Team-work, hard work and dedication along with a strong desire to get the job done, allowed us to complete the installation by 12:00am. This was just three hours after we started! It was truly a remarkable experience. The Py family was in a complete state of shock when they returned to their home. The Py Family episode initially aired on April 30, 2006 on ABC.

For more information on Extreme Makeover visit <http://abc.go.com/>



We're on the Web!

www.weaverprecast.com

Site Preparation Procedures: Prior to Installation STONE—Part One of Six

Following is basic information you or your builder will need to prepare your site for the installation of the Superior Wall System®. **It is Critical that your site be prepared Properly PRIOR to the delivery of your walls.**

Stone:

- Superior Walls *Must* be installed on *Virgin Soil*
- Stone is 1/2 inch, Clean, Crushed (AASHTO #8 recommended) NO LARGER
- Stone is graded evenly and is level to within 1 inch
- Stone depth is at least 6 inches (minimum requirement)
- Stone covers entire area where walls are to be set and is level
- Excavation has at least a 2 foot over dig (minimum requirement)
- Excavation cannot exceed 7'6" in depth, excavation over 7'6" in depth must include a 24" bench

